

SUPSHIP JACKSONVILLE
LOCAL STANDARD ITEM

FY-04

ITEM NO: 099-55JA
DATE: 01 NOV 2002
CATEGORY: I

1. SCOPE:

1.1 Title: Cleaning and Pumping; accomplish (RA/TA)

2. REFERENCES:

2.1 Standard Items

2.2 MIL-STD 777, Schedule of Piping, Valves, Fittings, and Associated Piping Components

2.3 802-5959353, MIL-STD-777 Modified for DDG-51 Class, Schedule of Piping, Valves, Fittings, and Associated Piping Components

2.4 S9086-T8-STM-010/CH-593, Pollution Control

2.5 S9542-AA-MMO-010, Shipboard Aviation JP-5 Fuel Systems

2.6 S9086-SP-STM-010/CH-542, Gasoline and JP-5 Fuel Systems

2.7 MIL-HDBK-291, Military Handbook Cargo Tank Cleaning

3. REQUIREMENTS:

3.1 Open, ventilate, empty, clean, render dry, and maintain any tank or space including adjacent tanks, spaces, or piping systems where the scope of repairs will result in a need for certification during the performance of this Job Order.

3.1.1 Ensure that harmful vapors, fumes, or mists are ventilated to the exterior of the vessel.

3.1.2 Install expandable plugs or blanks, painted blaze orange, in associated tank piping at the first valve or flange. Associated piping is defined as "an assembly of pipe, tubing, valves, fittings and related components forming a whole or a part of a system which starts or terminates in subject area, thus being common to and associated with same."

3.1.2.1 Submit **one legible copy, in hard copy or electronic media**, of a report listing the location of each expandable plug and blank to the SUPERVISOR.

3.1.2.2 Submit **one legible copy, in hard copy or electronic media**, of a report listing the location, origin, and quantity of each manhole cover removed in 3.1 in respect to its tank, ship's frame, and distance off centerline to the SUPERVISOR.

3.1.2.3 Remove each expandable plug or blank upon completion of repairs and testing, and install new gaskets and fasteners in accordance with applicable Categories and Group of 2.2 or 2.3.

3.1.3 Clean and disinfect each CHT/sewage tank and associated piping in accordance with 2.4.

3.1.3.1 Maintain one system for Ship's Force use at all times.

3.1.4 Clean each tank and any associated piping in accordance with 2.5 through 2.7.

3.2 Steam clean each area where the removal of preservative is required.

3.2.1 Install new rust preventative compound conforming to MIL-C-16173, Grade One.

3.2.2 Install new Monel fill and drain plugs conforming to QQ-N-281, Class B, to replace those removed to accomplish steam cleaning.

3.3 Pump tanks containing petroleum products to the low suction level of each tank.

3.3.1 Products shall be run through a flow meter calibrated in gallons.

3.3.2 Off-loading/on-loading of petroleum products shall be accomplished during daylight hours only.

3.3.3 Hoses, pumps, and storage containers shall be clean and dry prior to start of off-loading/on-loading.

3.3.4 Submit **one legible copy, in hard copy or electronic media**, of completed Attachment A (products inventory) to the SUPERVISOR.

3.3.5 Remove and dispose of liquids not being stored for reuse, including compensating sea water from the compensating fuel tanks, sludge, and debris in accordance with federal, state, and local laws, codes, ordinances, and regulations.

3.3.5.1 Fill the compensating fuel tanks with sea water upon completion of work.

3.4 Take samples of petroleum products from each tank or containment in accordance with 3.4.1 of 099-51JA prior to removal from ship and storage.

3.4.1 Accomplish analysis of petroleum products two working days prior to off-loading.

3.4.2 Accomplish a chemical analysis of each sample of distillate fuel and JP-5.

3.4.2.1 Test each sample for flashpoint, using the PENSKY-MARTENS method. The flashpoint should be in the range specified by 2.6.

3.4.2.2 Measure and record the API Gravity at 60 degrees Fahrenheit.

3.4.2.3 Check the bottom sediment and water, using a centrifuge. For distillate fuel, sediment and water should be less than 0.1 percent. For JP-5, sediment shall not be greater than 8 milligrams per liter and there should be no visible traces of water.

3.4.2.4 Measure the acid number. The acid number shall be within five percent of the original value upon return to ship.

3.4.2.5 Submit **one** legible copy, **in hard copy or electronic media**, of results of the analysis of 3.4.2 to the SUPERVISOR.

3.5 Off-load and store or off-load and transport to the nearest Naval Fuel Depot (NFD), at the discretion of the contractor based upon cost effectiveness, the distillate fuel and JP-5.

3.5.1 Notify the SUPERVISOR prior to transporting the off-loaded petroleum products.

3.5.2 Deliver to the nearest NFD when directed by the SUPERVISOR. Conveyance will be accepted from 0730 to 1600, Monday through Friday, holidays excluded. The NFD will accomplish a petroleum analysis requiring a time duration of one hour prior to off-loading each conveyance.

3.5.3 Notify the NFD Director a minimum of five working days prior to delivering the off-loaded petroleum products, via the SUPERVISOR.

3.5.4 Submit **one** legible copy, **in hard copy or electronic media**, of completed Attachment A, signed by the NFD Director, listing the amount and type of petroleum products received, to the SUPERVISOR within 24 hours after disposition.

3.5.5 Distillate fuel and JP-5 fuel off-loaded and stored by the contractor shall be sampled and analyzed in accordance with 3.4.1 through 3.4.2.4 prior to on-loading.

3.5.5.1 Submit *one* legible copy, *in hard copy or electronic media*, of each analysis to the SUPERVISOR prior to on-load.

3.5.6 Provide ship with same type, grade, and quantity of distillate fuel and JP-5 off-loaded and stored, when directed by the SUPERVISOR.

3.6 Off-load and store in clean storage containers the lube oil and hydraulic oil from the tanks. On-load when directed by the SUPERVISOR.

3.6.1 Accomplish the requirements of 009-63 of 2.1.

3.6.1.1 Test and analyze samples from each tank prior to off-loading.

3.6.1.2 Test and analyze samples from each storage container prior to on-loading.

(V)(G) "VERIFY OFF LOAD COORDINATION"

3.7 Coordinate the off loading or transferring of fluids through the ship's Damage Control Assistant (DCA), via the SUPERVISOR, to maintain ship's stability and to prevent flooding.

3.7.1 Obtain a list from the SUPERVISOR of petroleum soundings for tanks prior to start of pumping operations.

(V)(G) "VERIFY CLEAN CONTAINER"

3.7.2 Off-load and store petroleum products in the quantities noted in the Job Order.

3.8 Clean each bilge of spaces noted in the Job Order, free of trash, debris, grease, oily liquids, and other liquid contaminants prior to the initial certification.

3.8.1 Maintain each bilge to a clean, dry condition for the duration of the availability on a 7-day-a-week, 24-hour-a-day basis.

3.8.2 Remove and dispose of additional gallons of non-hazardous liquids from bilges as noted in the Job Order, generated by the Navy, after initial cleaning and certification is obtained. Removals shall be measured. Total amount of liquids removed greater or less than the above amount shall be the subject of an equitable adjustment.

(V)(G) "SOURCE DETERMINATION"

3.8.2.1 Submit **one** legible copy, **in hard copy or electronic media**, of a report listing the amount of gallons removed in 3.8.2, responsible source of liquids, and date liquids were removed after each pumping operation.

(V)(G) "CLEAN AND DRY BILGES"

3.8.3 Prior to space turnover, when directed by the SUPERVISOR, accomplish a final detergent cleaning of each bilge of spaces as noted in the Job Order, removing all trash, debris, grease, oily liquids, and other liquid contaminants from the bilges.

3.8.3.1 Reinstall and remove pumping equipment three evolutions after space turnover to support 3.8.1 and 3.8.2.

3.9 Clean each chain locker free of silt, mud, and foreign matter.

3.10 Dispose of liquids in accordance with federal, state and local laws, codes, ordinances or regulations.

3.11 Tank Closure Repairs:

3.11.1 Clean, chase, or tap threaded areas prior to installing covers.

3.11.2 Weld up, drill, and tap a total of 15 stripped manhole cover bolt holes for tanks opened in 3.1.

3.11.3 Remove existing and install new a total of 15 missing or broken manhole cover studs for tanks opened in 3.1 conforming to MIL-DTL-1222, Type IV, Grade 304.

3.11.4 Accomplish the requirements of 009-12 of 2.1, including Table 2, Columns A, B, C or D, Lines One through 7.

3.11.5 Accomplish the requirements of 009-32 of 2.1 for new and disturbed surfaces.

(V)(G) "INSPECT TANK CLEANLINESS"

3.12 Inspect each tank for cleanliness prior to final closing.

3.12.1 Submit **one** legible copy, **in hard copy or electronic media**, of a report listing the names of personnel present during inspection to the SUPERVISOR within 72 hours after completion of final closing.

3.12.2 Install manhole cover for each tank, using new gaskets conforming to MIL-C-6183, Class One, new CRES washers conforming to FF-W-92,

Type A, Grade One, Class B, and new brass nuts conforming to MIL-DTL-1222, Type One, Grade 464, and/or CRES hex head cap screws conforming to ASTM A307.

3.12.2.1 Install new gaskets conforming to ASTM D2000-75E, new hex nuts conforming to ASTM A307, and new hex head cap screws conforming to ASTM A307 for DDG-51 Class ships' sewage tanks.

3.12.2.2 Install new gaskets conforming to A-A-55759, Class 3A, Grade 30, and new hex head brass nuts conforming to MIL-DTL-1222, Type I, for DDG-51 Class ships' high temperature compartments.

3.12.2.3 Install new hex head, new self-locking nuts (nickel-copper) conforming to MIL-N-25027 for LSD-41 Class ships.

3.12.2.4 Install new cotton wax wicking to studs prior to installing washers and nuts for DDG-51 Class ships.

3.12.3 Install access cover for each potable water, feedwater, and sewage tank, using new gaskets conforming to MIL-~~PRF~~-1149, new nuts conforming to MIL-DTL-1222, Type I, Grade 5, zinc coated, and new CRES washers conforming to FF-W-92, Type A, Grade One, Class B.

3.12.4 Confirm that all personnel have exited the space prior to closure of tanks, voids, and cofferdams. Designate one person to account for all personnel who may have entered the space.

3.13 Accomplish the requirements of 009-32 of 2.1 for new and disturbed surfaces.

4. NOTES:

4.1 Location(s) of the Naval Fuel Depot(s) receiving off-loaded fuels is/are available from the SUPERVISOR.

4.2 For the purpose of this Work Item, the terms "tank" or "space" include voids, cofferdams, and inaccessible or confined areas.

4.3 Consider each bilge to contain contaminated oily salt water.

4.4 Booklet of General Plans and Tank Sounding Tables are available for review at the office of the SUPERVISOR.

INVENTORY SCHEDULE - PETROLEUM PRODUCTS

_____ LOT NO. _____

[illegible]

NFD DIRECTOR _____

CONTRACTOR/SUBCONTRACTOR AUTHORIZED REPRESENTATIVE _____

SHIP'S COMMANDING OFFICER'S AUTHORIZED REPRESENTATIVE _____